

Duolok® Tube Fittings TECHNICAL REPORT

Date:

TABLE OF CONTENTS

- 1.0 Introduction
 - 1.1 Scope
 - 1.2 References
 - 1.3 Test Specimen Description
 - 1.4 Summary
- 2.0 Test Procedures and Results
 - 2.1 Test 1
 - 2.2 Test 2
 - 2.3 Test 3
- 3.0 Test Equipment and Instrumentation
- 4.0 Quality Assurance Program
- 4.0 Attachments
 - A. Photographs
 - B. Test Data
 - C. Material Certs
 - D. Revisions

Report No:
Revision:
Total Pages:
Date:

SSP INTRODUCTION

Since its inception in 1926, SSP has exhibited an expertise in the precision machining of tight tolerance, high quality fitting components. In fact, SSP's historical reputation for product quality, service and performance is recognized across the country and around the world.

In 1986, SSP relocated to its 25-acre property in Twinsburg, Ohio Southeast of Cleveland in North America's manufacturing heartland. Within its modern 165,000 square foot manufacturing facility, SSP has developed the internal ability to control its manufacturing variables as much or more than any other fittings' manufacturer. SSP designs and produces its own specialty cutting tools to proprietary standards with a 5 axis CNC tool and cutter grinder, high speed 4 axis CNC machining centers and ultra precise EDM's to allow manufacturing to the most stringent dimensional tolerances and surface finishes. Additionally, SSP's tool making capability supports an internal hot, closed-die forging operation. SSP plans, controls and performs its own metal forging operations on all elbows, tees and crosses manufactured into SSP fittings, connectors and adapters. Indeed, SSP's production capacity is among the largest single-site facilities in the entire industry with the capability to allow one-of-a kind, "specials" machining on single spindle CNC's to high volume production on multi-spindle automatics.

Furthermore, SSP's ISO9001 Quality System Certification and Registration by DNV assures conformance to the highest levels of quality. The substantial investment of time and funds to obtain and maintain such status has paid dividends for SSP and its customers in efficiencies in process and supply.

In 2011 SSP unveiled a new line of valves called SSP Valves, as a direct alternative to the line of instrumentation valves manufactured by Swagelok. Following an ISO 9001 design process pattern, the critical elements of design planning, including the detailed documentation of design inputs and outputs occurred for the development of SSP Valves. Examples of such design inputs include:

Dimensional similarity
Material of construction similarity
Installation instruction similarity
Operation and performance similarity
Brand interchangeability
Corrosion resistance similarity
Applicable ANSI / ASME B 31.3 requirements

To accomplish the required design plan tasks of verification and validation, a specialized Technical Center was built within SSP. In addition to the exhaustive engineering calculations for confirmation of design conformance to industry standards and other engineering developed criteria, customized NIST traceable testing equipment was procured to allow:

Hydrostatic Proof and Burst Pressure Testing Air and/or Helium Pressure Testing

High Vacuum Testing
Cyclic Vibration Testing
Tensile Pull Testing
Hydraulic Impulse Testing
Thermal Cycle Testing
Low Temperature (Cryogenic) Testing
High Temperature Testing

Additional specific testing of Duolok with Swagelok, Parker CPI2 and Gyrolok2 was undertaken to confirm design compatibility and performance similarity, as well as competitive interchangeability and intermixability.

Examples of such additional testing includes:

Dimensional Measurement Comparison Installation Make-Up Torque Comparison Make-up Gageability Confirmation and Comparison

Conformance to the design engineering team's prescribed acceptance criteria allows the products' release for production and distribution to the marketplace.

1.0 INTRODUCTION

This document's purpose is to report, in a published format for public review, a representative sampling of the Duolok tube fitting's actual performance results from the Design Plan's Validation Tests. The performance results are measured against the Design Team's Approved Acceptance Criteria, which are based on meeting or exceeding the published and / or test-based performance of equivalent products from Swagelok and Parker. A positive testing performance of the products in the Validation Tests was required to complete the final element of the design cycle and provide for the Design Release of the Duolok product family.

1.1 SCOPE

Scope: Performance testing of Duolok 3/8" tube fittings. This test report documents the results of performance testing for the 3/8" Duolok tube fitting.

1.2 REFERENCES

- SSP No. QM06, "SSP Tech Center Laboratory Quality Manual"
- ISO 17025, "General Requirements for the Competence of Testing and Calibration Laboratories"
- ISO 9001:2008, "Quality Management Systems Requirements"
- ANSI/NCSL Z540-1, "Calibration Laboratories and Measuring and Test Equipment, General Requirements"
- ASTM F1387-99, "Standard Specification for Performance of Piping and Tubing Mechanically Attached Fittings"
- ISO 10012-1, "Quality Assurance Requirements for Measuring Equipment"
- MIL-STD-45662A, "Calibration System Requirements"
- SSP No. IP11, "Interchange Test"

1.3 TEST SPECEMIN DESCRIPTION

This test report will document all of the testing involved in the validation of the design for

Sample #

Heat Code (s)

1.4 SUMMARY

The table of contents lists the major Validation Tests that were performed, and the sections which follow describe the tests and outline specific results. All products manufactured at SSP are to approved and controlled engineering documentation, to established process and quality procedures at every stage of manufacture, with fully calibrated quality and process instrumentation, using only certified and traceable materials. Tested products were selected randomly from documented normal production runs. Before and after test samples were retained for reference. All tubing used in testing meets applicable ASTM specifications, and has approved material and chemical certifications.

In every case all Duolok test results met or exceeded the established Design Team's Acceptance Criteria for these products. As such, they also met or exceeded equivalent major competitive product performance, as measured in test data and / or reported in publications.

2.0 TEST PROCEDURES AND RESULTS

2.1: INITIAL MAKEUP TEST

Purpose: Test determines if the tube and fitting assembly has comparable levels of assembly torque to that of Swagelok and Parker, and achieves proper fitting makeup.

NOTE: Instrumentation Tube Fittings, due to the variances of tubing hardness and outside / inside diameters, require a certain geometric rotation of the tubing nut for proper makeup.

Assembly torque requirements vary per application and the level of torque is a general consideration, not a specification, for proper makeup.

Date:

Test Procedure: The fitting and tube are assembled per published standard fitting makeup instructions. Torque, in inch-pounds (or foot-pounds), vs. nut tightening rotation is recorded in ½ turn increments.



Figure 2.1.1 Initial Makeup: Torque Measurement




Figure 2.1.2 Initial Makeup: Fitting Assembly

Acceptance Criteria: Fitting is to achieve proper makeup, with average assembly torque being equal to or less than Swagelok2 / Parker2 results. See Example Acceptance Criteria in Table 3.1.1 below.

	Acceptance Criteria												
	Tubing / Fitting				Torque, in-lb								
Size	Wall (in)	WOrking Pres-		Revolutions									
0.20	,	sure (psig)	0.25	0.50	0.75	1.00	1.25						
6	0.035	3,300	30	87	123	173	234						
6	0.065	6,550	48	105	163	205	259						

Table 2.1.0, Acceptance Criteria

Test Results: Example results are shown in Table 3.1.2 below.

Results: Inital Makeup Torque Test

					Ini	itial Makeu	p Torque, ir	n-lb					
Sample	Size #	6	х	0.035"	Wall 1	Гubing	Size #	6	х	0.065"	Wall	Tubing	
No.		,	Revolution	ns	'	Pass Fail		•	Revolutio	ns	•	Pass Fail	Test
	0.25	0.50	0.75	1.00	1.25	P/F	0.25	0.50	0.75	1.00	1.25	P/F	
1	10	40	60	80	120	Р	10	40	65	105	150	Р	
2	10	40	55	80	140	Р	10	50	70	110	160	Р	D:+-
3	10	40	55	75	125	Р	10	45	70	105	150	Р	Bite
4	10	35	55	80	125	Р	15	60	90	130	170	Р	
1	5	30	50	80	125	Р	10	45	70	100	155	Р	
2	10	30	50	80	125	Р	15	5	80	125	175	Р	
3	10	35	55	80	135	Р	15	50	70	100	150	Р	Tension
4	10	40	55	110	160	Р	10	45	75	125	195	Р	
5	5	40	65	90	140	Р	10	50	70	110	165	Р	
1	10	40	60	75	115	Р	10	50	70	105	165	Р	
2	10	35	60	85	135	Р	10	50	75	115	165	Р	
3	10	35	50	75	125	Р	10	45	70	105	160	Р	
4	10	40	55	85	135	Р	10	50	80	110	175	Р	
5	10	50	90	120	180	Р	10	50	80	125	185	Р	
6	10	40	60	80	130	Р	10	50	75	100	160	Р	Gas
7	10	40	55	80	120	Р	10	45	75	115	175	Р	Leak
8	10	40	60	85	145	Р	10	50	80	115	170	Р	
9	10	35	60	80	130	Р	10	50	75	105	155	Р	
10	10	40	70	90	145	Р	10	45	65	95	145	Р	
11	10	35	55	80	130	Р	10	45	70	100	145	Р	
12	10	40	60	90	150	Р	10	40	65	100	155	Р	
1	10	35	50	80	125	Р	15	50	70	110	160	Р	
2	10	40	60	90	135	Р	20	55	80	115	165	Р	
3	10	45	65	85	140	Р	15	50	75	115	165	Р	Thermal Cycle
4	10	40	60	85	145	Р	15	60	90	130	180	Р	-,
5	20	40	65	90	145	Р	15	50	80	120	155	Р	
1	5	35	55	95	130	Р	10	50	75	105	155	Р	
2	5	40	55	85	130	Р	10	40	70	110	155	Р	
3	10	40	60	80	135	Р	10	50	70	110	165	Р	Remake
4	10	35	55	90	145	Р	10	40	70	105	155	Р	кетпаке
5	10	40	60	80	125	Р	10	50	75	105	160	Р	
6	10	40	65	90	140	Р	10	50	75	110	170	Р	

CONCLUSIONS: ALL DUOLOK ASSEMBLIES MET OR

EXCEEDED THE APPROVED ACCEPTANCE CRITERIA.

SECTION 3.2: HYDROSTATIC BURST PRESSURE TEST

Purpose: Test determines if the tube fitting assembly has adequate pressure-retaining capability, based on the ANSI / ASME B 31.3 maximum allowable working pressure of the tubing.

Equipment & Configuration: Two fittings are tested at a time – one on each end of a 4 %" long test tube, per Initial Makeup Test (see Section 3). Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figures 3.2.1 - 3.





Figure 3.2.1 - 2, Burst Test Configuration



Figure 3.2.3, Burst Test Specimen

Test Procedure: The tube fitting assembly is hydrostatically pressurized in regular pressure increments which increase until tube burst is attained. The digitally displayed maximum pressure, in PSIG, - at which the tubing bursts or tubing pushes out of the fitting - is recorded.

Report No: Revision: Total Pages:

Date:

ACCEPTANCE CRITERIA: THE TUBE FITTING ASSEMBLY IS TO SUSTAIN A HYDROSTATIC PRESSURE, WITHOUT OBSERVED LEAKAGE, EXCEEDING A MINIMUM OF 4 TIMES THE ANSI / ASME MAXIMUM ALLOWABLE WORKING PRESSURE OF THE TUBING. FAILURE IS TO BE BY TUBING BURST, NOT BY TUBE PUSHOUT FROM FITTING.

TEST RESULTS: EXAMPLE RESULTS ARE SHOWN IN TABLE 3.2.0 BELOW.

Results: Burst Test (Sample - Tube ends: A, B)

	Sampl	e No.	Tubing	/ Fitting	Acceptan	ce Criteria		Burst Test	
Test	А	В	Size	Wall	W.P.	Burst = 4 x W.P.	Actual burst	Fail Type	Pass / Fail
	#	#	#	in.	psig	psig	psig	n/a	P/F
	1	2					16,530		Р
	3	4					16520		Р
	5	6		0.035	3,300	13,200	16540		Р
	7	8		0.055	3,300	13,200	16520		Р
	9	10					16,730		Р
Impulse	11	12	6				16,730		Р
iiiipuise	1	2	0				29,840		Р
	3	4					29,770		Р
	5	6		0.065	6,550	26,200	29,900		Р
	7	8		0.003	0,550	20,200	29,820		Р
	9	10					29,820		Р
	11	12					30,190		Р
	1	2					16,450		Р
	3	4		0.035	3,300	13,200	16,710	Tube	Р
Remake	5	6	6				16,730		Р
Nemake	1	2	U				29,580		Р
	3	4		0.065	6,550	26,200	29,380		Р
	5	6					29,700		Р
	1						16,230		Р
Vibration	2		6	0.035	3,300	13,200	16,440		Р
	3						16,500		Р
	1						29,980		Р
	2						29,360		Р
Caps	3		6	0.065	6,550	26,200	29,640		Р
	4			0.003	0,550	20,200	29,980		Р
	5						29,920		Р
	6						29,420		Р

NOTE: A.C. = Acceptance Criteria

Table 3.2.0, Example Burst Test Results

CONCLUSIONS: ALL DUOLOK ASSEMBLIES MET OR EXCEEDED THE APPROVED ACCEPTANCE CRITERIA. ALL DUOLOK TUBE FITTINGS SUSTAINED THE REQUIRED MAXIMUM ALLOWABLE WORKING PRESSURE WITHOUT LEAKAGE, AND HELD LEAK FREE TO TUBING BURST, WITHOUT EXHIBITING TUBE PUSH OUT FROM THE FITTING.

SECTION 3.3: HYDRAULIC IMPULSE TEST

Purpose: Test determines if the tube fitting assembly can sustain extended pressure-cycling without leakage.

EQUIPMENT & CONFIGURATION: FOR EACH STAND MANIFOLD POSITION, TWO FITTINGS ARE TESTED AT A TIME - ONE ON EACH END OF A TEST TUBE PIECE. BOTH MINIMUM AND MAXIMUM RECOMMENDED WALL TUBING (WORST CASE CONDITIONS) ARE USED FOR EACH TESTED PRODUCT CONFIGURATION. SEE FIGURES 3.3.1-2.





Figure 3.3.1 - 2, Hydraulic Impulse Test Stand and Fixture

Test Procedure: The tube fitting assembly is pressurized with hydraulic test oil in a manifold with up to 24 fittings. The hydraulic fluid temperature and the pressure cycle envelope conform to MIL-H-24135 test specification. Peak test pressure is 5,250 PSIG, sustained at 30 cycles/minute. Test oil temperature is maintained between 120°F-125°F. Following the Hydraulic Impulse Test, samples are also subjected to Burst Test.

ACCEPTANCE CRITERIA:

Hydraulic Impulse Test: The tube fitting assembly is to sustain pressure cycling without observed leakage for 150,000 test cycles.

Burst Test: The tube fitting assembly is to sustain a hydrostatic pressure, without observed leakage, exceeding a minimum of 4 times the ANSI / ASME maximum allowable working pressure of the tubing. Failure is to be by tubing burst, not by tube pushout from fitting.

Test Results: Example results are shown in Table 3.3.0 below.

Results: Impulse Test, followed by Burst Test:

	Samp	le No.	Tubing	/ Fitting	Acce	ptance Cri	teria	li	mpulse Tes	t
Test	А	В	Size	Wall	Impulse Cycles	Test Press.	Leak	Cycles Without Failure	Leak	Pass / Fail
	#	#	#	in.	Cycles	psig	Leak / None	Cycles x 10 ³	Leak / None	P/F
	1	2						150	None	Р
	3	4						150	None	Р
	5	6		0.035 150,000	150,000 5,250	None	150	None	Р	
	7	8			0.055 150,000	3,230	None	150	None	Р
	9	10						150	None	Р
Impulse	11	12	6					150	None	Р
iiiipuise	1	2	0					150	None	Р
	3	4						150	None	Р
	5	6		0.065	150,000	5,250	None	150	None	Р
	7	8			130,000	3,230	INOTIE	150	None	Р
	9	10						150	None	Р
	11	12						150	None	Р

	Samp	e No.	Tubing	/ Fitting	Acceptan	ce Criteria		Burst Test	
Test	Α	В	Size	Wall	W.P.	Burst = 4 x W.P.	Actual burst	Fail Type	Pass / Fail
	#	#	#	in.	psig	psig	psig	n/a	P/F
	1	2					16,530		Р
	3	4					16,520		Р
	5	6		0.025	3,300	13,200	16,540		Р
	7	8	0.035	3,300	13,200	16,520		Р	
	9	10					16,730		Р
Impulso	11	12	6				16,730	Tube	Р
Impulse	1	2	0				29,840	Tube	Р
	3	4					29,770		Р
	5	6		0.065	6 550	26 200	29,900		Р
	7	8		0.065	6,550	26,200	29,820		Р
	9	10					29,820		Р
	11	12					30,190		Р

NOTE: A.C. = Acceptance Criteria

Table 3.3.0, Example Hydraulic Impulse and Burst Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. No leakage or rupture of a Duolok tube fitting assembly was observed.

SECTION 3.3: HYDRAULIC IMPULSE TEST

Purpose: Test determines capability of the tube fitting assembly to successfully seal after repeated assembly and disassembly of a made-up tube assembly with a mating fitting. This test simulates the normal use condition where fittings are repeatedly disassembled from fittings for fluid system service or maintenance, and reassembled with additional tightening.

EQUIPMENT & CONFIGURATION: Two fittings are tested at a time – one on each end of a 4 ½" long test tube, per Initial Makeup Test (see Section 3). Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figure 3.4.1, Repeated Remake Test



Figure 3.4.1, Repeated Remake Test (Size 8 Duolok)

Test Procedure: To simulate repeated remake conditions, the tube fitting is disassembled and assembled (tightening from the preceding installation position an additional 1/12 turn – or 30 each time) at each reassembly, for five successive times. This is followed by air pressure testing to the maximum recommended working pressure of the tubing, under water to observe leakage. After each disassembly of the tube fitting assembly it is examined for absence of the following Remake Failure Criteria:

Tube Sticking, Body Swelling, Nut Sticking, Thread Galling, Ferrule Set, Ferrule Galling, Body Denting, Excessive Torque, Tube pushout or burst.

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain an air booster test pressure, PSIG, of the ANSI / ASME maximum allowable working pressure of the tubing, up to a maximum pressure of 10,000 PSIG. Failure is either any observed air leakage bubble, or the presence of any of the above Remake Failure Criteria.

Report No: Revision:

Total Pages:

Date:

Test Results: Example results are shown in Table 3.4.0 below.

Results: Remake Gas Leak Tests

		Gas Le	ak Test			
 Tubing	g Size #			 6		
	g Wall:	0.03		0.06	5 in.	
	Test Press.		D psig	6,600		
Acceptano	ce Criteria:			Leak		
Sample	Remake	Leak	Pass / Fail	Leak	Pass / Fail	
#	#	Leak / None	P/F	Leak / None	P / F	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
1	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
2	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
3	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
4	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
5	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	
	1	None	Р	None	Р	
	2	None	Р	None	Р	
6	3	None	Р	None	Р	
	4	None	Р	None	Р	
	5	None	Р	None	Р	

Table 3.4.0, Example Repeated Remake Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. No leakage or Remake failures were observed in any Duolok tube fitting assemblies.

Section 3.5: Tension Test

Purpose: Test determines if the tube fitting assembly has the capability to sustain axial forces equivalent to the hydrostatic end force caused by approaching four times tubing working pressure. This test simulates end loading of straight, stiff, tube assemblies subjected to high end loads, as occur with structural deflection and thermal expansions.

EQUIPMENT & CONFIGURATION: One fitting is assembled on the end of a test tube, per Initial Makeup Test (see Section 3). Tensile loads are applied by a Tensile Test machine. Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figure 3.5.1.




Figure 3.5.1, Tension Test Configuration.

Test Procedure: The tube fitting assembly is axially loaded in tension, and increasing loads are applied until tubing pull out is observed. The maximum load sustained by the fitting, in pounds, is recorded by digital force instrumentation.

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain an end force approaching that equivalent to the end force produced by 4 times the ANSI / ASME maximum allowable working pressure of the tubing. Failure is a pull out force less than this equivalent end load.

Date:

Test Results: Example results are shown in Table 3.5.0 below.

Results: Tension Test

Sample	Tubing /	Fitting		Acceptance Criteria	Tension Test						
No.	Size	Wall	W.P.	Burst = 4 x W.P. (Basis of Pullout Force)	Tubing O.D.	Pullout Force (Based on 4 x W.P.)	Actual Pullout Force	Fail Type	Pass / Fail		
#	#	in.	psig	psig	in.	lb	lb	#	P/F		
1					0.3755	1,462	1,850	1	Р		
2					0.3755	1,462	1,800	1	Р		
3	6	0.035	3,300	13,200	0.3755	1,462	1,994	1	Р		
4					0.3755	1,462	2,464	1	Р		
5					0.3755	1,462	1,712	1	Р		

NOTE: A.C. = Acceptance Criteria

FAIL TYPE #:

- *1 Pullout
- *2 Broke in Tension at the rear ferrule.
- *3 Tube broke in Tension at mid-length.

Table 3.5.0, Example Tension Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. Observed pull out forces generally exceeded the equivalent of four times tubing working pressure for all Duolok tube fitting assemblies.

Section 3.6: Vibration Test

Purpose: Test determines if the tube fitting assembly has high resistance to vibration-based fatigue when simultaneously exposed to 1.6 times tubing maximum allowable working pressure, based on the ANSI / ASME B 31.3 maximum allowable working pressure of the tubing.

EQUIPMENT & CONFIGURATION: One fitting is tested at a time in each station of the stand. The fitting is assembled to one end of a test tube, made up per Initial Makeup Test (see Section 3). A small format strain gage is mounted axially on the tube next to the fitting nut, and the gage is read by peak stress detecting strain gage instrumentation. A motor coaxial to the fitting axis turns a faceplate containing a spherical bearing that is radially offset to produce cyclic strain on the tested tube fitting assembly.

Minimum recommended wall tubing (worst case condition) is used for each tested product configuration. See Figures 3.6.1 - 2.






Figure 3.6.1 - 2, Vibration Test Stand and Test Configuration

Test Procedure: The motor faceplate is adjusted to produce a maximum stress adjacent the tube fitting nut equal to 60% of the tubing yield stress (YS), in KSI, as digitally indicated on the strain gage instrumentation. The tube fitting assembly is hydrostatically pressurized to 1.6 times the tubing maximum allowable working pressure and isolated from the pump by a valve. A digital counter counts revolutions of the motor faceplate (equal to the number of complete stress cycles from maximum tensile to maximum compressive stress of 60% of YS). A pressure switch stops the test on any loss of pressure during the test.

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain a combination of hydrostatic pressure equal to 1.6 times the ANSI / ASME maximum allowable working pressure of the tubing, and 10 million stress cycles. Failure is any loss of pressure in the tube fitting assembly.

Report No: Revision:

Total Pages:

Date:

Test Results: Example results are shown in Table 3.6.0 below.

Configuration: Vibration Test

	Strain Gage Data:	
Item	Value	Unit
Lot number:	R-A48BE13	n/a
Stock number:	EA-09-062EN-350	n/a
Gage factor:	2.085 ± 0.5% @ 24°C	dmls
Gage Excitation Voltage:	5	V
Peak Stress value:	17,000	psi
Modulus of Elasticity:	29,000,000	psi
Strain setting:	586.2	με

Results: Vibration Test

	Sample	Tubing ,	/ Fitting	Aco	Acceptance Criteria			Vibration Test			
Test	Sample No.	Size	Wall	Vibr. Cycles	Test Press.	Leak	Cycles without Failure	Leak	Pass / Fail		
	#	#	in.	Cycles	psig	Leak / None	Cycles x 10 ⁶	Leak / None	Pass / Fail		
	1						10	None	Р		
Vibration	2	6	0.035	10,000,000	5,280	None	10	None	Р		
	3						10	None	Р		

Results: Burst Test after Vibration Test

	Sample		Tubing	/ Fitting	Burst Test			
Test	No.	Size	Wall	W.P.	Burst A.C. = 4 x W.P.	Actual Burst	Fail Type	Pass / Fail
	#	#	in.	psig	psig	psig	n/a	Pass / Fail
	1					16,230	Tube	Р
Vibration	2	6	0.035	3,300	13,200	16,440	Tube	Р
	3					16,500	Tube	Р

NOTE: A.C. = Acceptance Criteria

Table 3.6.0, Example Vibration Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. No observed leaks or loss of pressure occurred in any Duolok tube fitting assemblies.

Section 3.7: Intermix Test

Purpose: Test determines if all combinations of tube fitting components (nut, back ferrule, front ferrule and fitting body) of Duolok and Swagelokcan be intermixed in a tube fitting assembly, resulting in both adequate gas and liquid pressure-retaining capability, based on ANSI / ASME B 31.3 maximum allowable working pressure of the tubing.

This test simulates the random intermixing of inventoried Duolok and Swagelok fitting components in the field to make up tube fitting assemblies.

EQUIPMENT & CONFIGURATION: Two fittings of a given combination of fitting components are tested at a time – one on each end of a $4\,\%$ " long test tube, per Initial Makeup Test (see Section 3). Maximum recommended wall tubing (worst case condition) is used for each tested product configuration. See Figure 3.7.1, and Table 3.7.1.



Figure 3.7.1, Intermix Test Configuration.

Commonwell				Combination			
Components	1	2	3	4	5	6	7
Body	Swagelok	Swagelok	Swagelok	Duolok	Swagelok	Duolok	Swagelok
Front Ferrule	Swagelok	Swagelok	Duolok	Swagelok	Swagelok	Duolok	Duolok
Back Ferrule	Swagelok	Duolok	Swagelok	Swagelok	Duolok	Swagelok	Duolok
Nut	Duolok	Swagelok	Swagelok	Swagelok	Duolok	Swagelok	Duolok

Campanants				Combination			
Components	8	9	10	11	12	13	14
Body	Duolok	Duolok	Duolok	Swagelok	Duolok	Swagelok	Duolok
Front Ferrule	Duolok	Duolok	Swagelok	Duolok	Swagelok	Duolok	Swagelok
Back Ferrule	Duolok	Swagelok	Duolok	Duolok	Swagelok	Swagelok	Duolok
Nut	Swagelok	Duolok	Duolok	Swagelok	Duolok	Duolok	Swagelok

Figure 3.7.1, Intermix Test Combinations

Report No:

Revision:

Total Pages:

Test Procedure: The tube fitting assembly is subjected to the Gas Leak Test (see Section 3.9), and then the Burst Test (see Section 3.2).

Date:

ACCEPTANCE CRITERIA: Gas Leak Test:

The tube fitting assembly is to sustain an air booster test pressure, PSIG, of the ANSI / ASME maximum allowable working pressure of the tubing, up to a maximum pressure of 10,000 PSIG. Failure is any observed air leakage bubble.

Burst Test: The motor faceplate is adjusted to produce a maximum stress adjacent the tube fitting nut equal to 60% of the tubing yield stress (YS), in KSI, as digitally indicated on the strain gage instrumentation. The tube fitting assembly is hydrostatically pressurized to 1.6 times the tubing maximum allowable working pressure and isolated from the pump by a valve. A digital counter counts revolutions of the motor faceplate (equal to the number of complete stress cycles from maximum tensile to maximum compressive stress of 60% of YS). A pressure switch stops the test on any loss of pressure during the test.

Test Results: Example results are shown in Table 3.6.0 below.

Configuration: Vibration Test

	Tubing ,	/ Fitting		Accep	tance Criteria	a		Gas Leak	Test		Burst Test			
Sample	Size No.	Wall	W.P.	Burst = 4 x W.P.	Gas Leak Press.	Leak	Combination	Leak	Pass / Fail	Actual Burst	Fail Type	Pass Fail		
#	#	in.	psig	psig	psig	Leak / None	#	Leak / None	P/F	psig	n/a	P/F		
1							1	None	Р	29,930	Tube	Р		
2							1	None	Р	29,930	Tube	Р		
3						_	None	Р	29,970	Tube	Р			
4						2	None	Р	29,970	Tube	Р			
5								3	None	Р	30,190	Tube	Р	
6							3	None	Р	30,190	Tube	Р		
7									_	None	Р	29,680	Tube	Р
8		0.005	C 550	26 200	6.550		4	None	Р	29,680	Tube	Р		
9	6	0.065	6,550	26,200	6,550	None	_	None	Р	29,990	Tube	Р		
10							5	None	Р	29,990	Tube	Р		
11								None	Р	29,910	Tube	Р		
12							6	None	Р	29,910	Tube	Р		
13							7	None	Р	30,280	Tube	Р		
14							7	None	Р	30,280	Tube	Р		
15							0	None	Р	29,800	Tube	Р		
16							8	None	Р	29,800	Tube	Р		

Table 3.7.2, Example Intermix Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. All Duolok tube fittings sustained the required maximum allowable working pressure without leakage, and held leak free to tubing burst without exhibiting tube push out from the fitting.

Section 3.8: Interchange Test

Purpose: Test determines if all combinations of both a tube fitting body and a tubing assembly (tube, nut, back ferrule, and front ferrule, assembled together per standard assembly instructions) of Duolok and a competitive fitting brand can be Interchanged in a complete tube fitting assembly, resulting in both adequate gas and liquid pressure-retaining capability, based on ANSI / ASME B 31.3 maximum allowable working pressure of the tubing.

This test simulates the interchange of fitting bodies with already made up tube assemblies in the field, for components from either Duolok, Swagelok, Parker CPI or Hoke Gyrolok fittings.

EQUIPMENT & CONFIGURATION: Two fittings of a given combination of fitting components are tested at a time – one on each end of a 4 $\frac{1}{2}$ " long test tube, per Initial Makeup Test (see Section 3). Maximum recommended wall tubing (worst case condition) is used for each tested product configuration. See Figures 3.8.1 - 2.




Figure 3.8.1, Interchange Test Combinations



Figure 3.8.2, Interchange Test Fittings and Components

Test Procedure: The tube fitting assembly is subjected to the Gas Leak Test (see Section 3.9), and then the Burst Test (see Section 3.2).

ACCEPTANCE CRITERIA:

Gas Leak Test:

The tube fitting assembly is to sustain an air booster test pressure, PSIG, of the ANSI / ASME maximum allowable working pressure of the tubing, up to a maximum pressure of 10,000 PSIG. Failure is any observed air leakage bubble.

Burst Test: The tube fitting assembly is to sustain a hydrostatic pressure, without observed leakage, exceeding a minimum of 4 times the ANSI / ASME maximum allowable working pressure of the tubing. Failure is to be by tubing burst, not by tube pushout from fitting.

Test Results: Example results are shown in Table 3.8.0 below.

Results: Interchange Test

	Tubing ,	/ Fitting		Accepta	nce Criteria		Combina	ations:	Gas Lea	ık Test	Burst Test		
Sample	Size No.	Wall	W.P.	Burst =4 x W.P.	Gas Leak Press.	Leak	Nut & Ferrule (s)	Body	Leak	Pass / Fail	Actual Burst	Fail Type	Pass Fail
#	#	in.	psig	psig	psig	Leak / None	Name	Name	Leak / None	P/F	psig	n/a	P/F
1							Swagelok	Swagelok Duolok	None	Р	29,600	Tube	Р
2									None	Р	29,600	Tube	Р
3						-	Gyrolok Duolok	None	Р	29,860	Tube	Р	
4								Duolok	None	Р	29,860	Tube	Р
5							СРІ	CPI Duolok	None	Р	29,720	Tube	Р
6		0.005	6.550	26 200	6.550				None	Р	29,720	Tube	Р
7	6	0.065	6,550	26,200	6,550	None			None	Р	29,720	Tube	Р
8							Duolok	CPI	None	Р	29,720	Tube	Р
9							D -1-1	6	None	Р	29,790	Tube	Р
10						Duolok	Duolok Swagelok	None	Р	29,790	Tube	Р	
11							D -1-1	6	None	Р	30,140	Tube	Р
12							Duolok	Gyrolok	None	Р	30,140	Tube	Р

Table 3.8.0 Example Interchange Test Results

CONCLUSIONS: All interchanged Duolok assemblies met or exceeded the approved Acceptance Criteria. All Duolok tube fittings sustained the required maximum allowable working pressure without leakage, and held leak free to tubing burst without exhibiting tube push out from the fitting.

Section 3.9: Gas Leak Test

Purpose: Test determines if the tube fitting assembly has adequate gas pressure-retaining capability, based on the ANSI / ASME B 31.3 maximum allowable working pressure of the tubing.

EQUIPMENT & CONFIGURATION: Two fittings are tested at a time – one on each end of a $4\,\%$ " long test tube, per Initial Makeup Test (see Section 3). Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figure 3.9.1 - 2, Gas Leak Test Configuration.





Figure 3.9.1 - 2, Gas Leak Test Configuration.

Test Procedure: The tube fitting assembly is pressurized, under water, with air in regular pressure increments to the lower of either the maximum allowable working pressure of the tubing or 10,000 PSIG, is attained. This pressure is held for a minimum of five minutes. The digitally displayed maximum pressure, in PSIG, is recorded

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain an air booster test pressure, PSIG, of the ANSI / ASME maximum allowable working pressure of the tubing, up to a maximum pressure of 10,000 PSIG. Failure is any observed air leakage bubble.

Test Results: Example results are shown in Table 3.9.0 below.

Results: Gas Leak Test

	Samp	le No.	Tubing	/ Fitting		Acceptan		Gas Leak Test		
Test	А	В	Size	Wall	W.P.	Burst = 4 x W.P.	Test Press.	Leak	A.C. Leak	Pass / Fail
	#	#	#	in.	psig	psig	psig	Leak / None	Leak / None	P/F
	1	2				13,200	3,300	None	None	Р
	3	4							None	Р
	5	6		0.035	3,300				None	Р
	7	8		0.035					None	Р
	9	10							None	Р
Gas Leak	11	12	6						None	Р
Gas Leak	1	2	0					None	None	Р
	3	4							None	Р
	5	6		0.065	6.550	26 200	6 550		None	Р
	7	8		0.005	6,550	26,200	6,550		None	Р
	9	10							None	Р
	11	12							None	Р

NOTE: A.C. = Acceptance Criteria

Table 3.9.0 Example Gas Leak Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. No Duolok tube fitting assemblies developed observable Gas Leakage.

Section 3.10: Thermal Cycle, Thermal Shock Test

Date:

Purpose: Test determines if the tube fitting assembly has the capability to sustain substantial and rapid temperature cycling while maintaining vacuum and pressure retention capabilities.

EQUIPMENT & CONFIGURATION: One fitting is tested at a time on the end of a test tube, assembled per Initial Makeup Test (see Section 3). Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figure 3.10.1 - 2, Thermal Cycle, Thermal Shock Test Configuration.






Figure 3.9.1 - 2, Gas Leak Test Configuration.

Test Procedure: A thermocouple is directly attached to the fitting to ensure accurate achievement of test temperature. The tube fitting assembly is pressurized with air to 1,000 PSIG, and simultaneously heated in a tubular furnace to 1,000 F (538 C). The digitally displayed maximum pressure, in PSIG, and temperature is recorded. On reaching both pressure and temperature the tube fitting assembly is removed and rapidly cooled to ambient temperature. This cycle is repeated three times.

The above thermal cycling is followed by a vacuum test whereby a high vacuum is drawn on the inside of the fitting by Vacuum Test Equipment, helium gas is sprayed over the outside of the fitting and a leakage rate is recorded.

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain the above thermal cycling under air pressure, and after quenching to room temperature not exhibit any detectable leakage when immersed in water. Additionally, when subsequently subjected to the vacuum test, the fitting must not exhibit a helium vacuum test leak rate in excess of $< 4 \times 10-9$ mbar l/s.

Test Results: Example results are shown in Table 3.10.0 below.

Results: Thermal Cycle, Vacuum Tests

	Tuk	oing	A	cceptance Criter	ia		Vacuu	m Test
Sample	Size No.	Wall	Temperature Range	Test Press.	Leak Rate	Cycle No.	Actual Leak Rate	Pass / Fail
#	in.	in.	°F	psig	atm cc/s	#	atm cc/s	P / F
						1		
1						2		
						3	6.0E-10	Р
						1		
2		0.035	Amb. to 1,000	1,000	1.00E-09	2		
			_,,,,,			3	2.8E-10	Р
						1		
3						2		
	6					3	5.0E-10	Р
	0					1		
1						2		
						3	3.2E-10	Р
						1		
2		0.065	Amb. to 1,000	1,000	1.00E-09	2		
			2,000			3	4.0E-10	Р
						1		
3						2		
						3	4.3E-10	Р

NOTE: A.C. = Acceptance Criteria

Table 3.10.0 Example Thermal Cycle Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. Observed leak rates of tested Duolok tube fitting assemblies performed consistently better than the required Acceptance Criteria, and published competitive results.

Section 3.11: Vacuum Test

Purpose: Test determines if the tube fitting assembly has the capability to seal at high vacuums, with ultra low leakage rates.

EQUIPMENT & CONFIGURATION: One fitting is tested at a time on the end of a test tube, assembled per Initial Makeup Test (see Section 3). Both minimum and maximum recommended wall tubing (worst case conditions) are used for each tested product configuration. See Figure 3.11.1 - 2, Vacuum Test Configuration.





Figure 3.11.1 - 2, Vacuum Test Configuration

The Leak Rate Sensitivity of the Veeco MS-40 Helium Leak Detection Test Equipment is 4.0 x 10-11 mbar l/s. Duolok fittings have been tested and shown results in the 10-11 mbar l/s range.

Test Port pressures are displayed in units of milli-Torr. The vacuum levels developed during testing are as low as 4 mT - 9mT. This equates to an absolute pressure of .0000744 - 0.000174 PSIA.

Test Procedure: The internal volume of the tube fitting assembly is evacuated to a vacuum of 4 mT – 9 mT (milliTorr). The digitally displayed vacuum pressure, in mT, is recorded. On achieving full vacuum pressure, helium gas is sprayed around the outside of the fitting, and the leakage rate is recorded.

Report No:


Revision:

Total Pages:

Date:

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain the above vacuum pressure, and not exhibit a helium test leak rate in excess of < 4 x 10-9 mbar l/s.



Test Results: Example results are shown in Table 3.11.0 below.

Results: Vacuum Leak Test

Samp	le No.	Tubing	/ Fitting	A.C.	Vacuum Leak Test		st
Α	В	Size	Wall	Leak Rate	Port Vac.	Leak Rate	Pass / Fail
#	#	#	in.	atm-cc/s	mT	atm-cc/s	P/F
1	2				4	8.00E-10	Р
3	4				4	7.00E-10	Р
5	6		0.035	4 005 00	4	5.50E-10	Р
7	8		0.035	1.00E-08	4	1.30E-10	Р
9	10				4	1.40E-10	Р
11	12	6			4	6.50E-10	Р
1	2	0			4	7.00E-10	Р
3	4				4	1.90E-09	Р
5	6		0.005	1 005 00	4	8.00E-10	Р
7	8		0.065	1.00E-08	4	6.70E-10	Р
9	10				4	6.00E-10	Р
11	12				4		Р

NOTE: A.C. = Acceptance Criteria

Table 3.11.0 Example Vacuum Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. Observed leak rates of tested Duolok tube fitting assemblies performed consistently better than the required Acceptance Criteria, and published competitive results.

Section 3.12: Low Temperature (Cryogenic) Helium Leak Test

Purpose: Test determines if the tube fitting assembly has the capability to seal in low temperature (cryogenic) applications with ultra low leakage rates.

EQUIPMENT & CONFIGURATION: One fitting is tested at a time on the end of a test tube, assembled per Initial Makeup Test (see Section 3). Minimum recommended wall tubing (worst case condition) is used for each tested product configuration. See Figure 3.12.1, Low Temperature Helium Leak Test Configuration.



Figure 3.12.1, Low Temperature Helium Leak Test Configuration.

The Leak Rate Sensitivity of the Veeco MS-40 40 Helium Leak Detection Test Equipment is 4.0 x 10-11 std cc/sec. Duolok tube fittings have been tested and shown results in the 10-11 mbar l/s range.

Test Port pressures are displayed in units of milli-Torr. The vacuum levels developed during testing are as low as 4 mT - 9mT. This equates to an absolute pressure of .0000744 - 0.000174 PSIA.

Test Procedure: The tube fitting assembly is immersed in a liquid nitrogen bath, -320 F (-196 C), and the internal volume of the tube fitting assembly is evacuated to a vacuum of 4 mT – 9 mT (milliTorr). The digitally displayed Low Temperature Helium Leak pressure, in mT, is recorded. Helium is also cooled to the liquid nitrogen temperature before being sprayed on the cold fitting exterior. On achieving full Low Temperature Helium Leak pressure, -320 F (-196 C) helium gas is sprayed around the outside of the fitting, and the leakage rate is recorded.





Figure 3.12.2, Low Temperature Helium Leak Test Sequence.

ACCEPTANCE CRITERIA:

The tube fitting assembly is to sustain the above low temperature, and not exhibit a helium test leak rate in excess of $< 4 \times 10-9$ mbar l/s.



Test Results: Example results are shown in Table 3.12.0 below.

Results: Low Temerature Leak Test

Sample	Tubing ,	/ Fitting	Acceptance Criteria		Low Temperature Test				
Sample	Size	Wall	A.C. Leak Rate	Test Port Vacuum	Test Temp.	Low Temp. Leak Rate	Pass / Fail		
#	#	in.	mbar l/s	mT	°F	Mbar l/s	P/F		
1				4	-310	3.24E-10	Р		
2				1	-310	4.36E-10	Р		
3				4	-310	5.27E-10	Р		
4				4	-310	3.45E-10	Р		
5	6	0.035		4	-310	4.46E-10	Р		
6	б	0.035	4.00E-09	4	-310	1.72E-10	Р		
7				4	-310	3.65E-10	Р		
8				4	-310	6.69E-10	Р		
9				4	-310	2.63E-10	Р		
10				4	-310	5.17E-10	Р		

Average: 4.06E-10
Standard Deviation: 1.44E-10

NOTE: A.C. = Acceptance Criteria

Table 3.12.0 Example Low Temperature Leak Test Results

CONCLUSIONS: All Duolok assemblies met or exceeded the approved Acceptance Criteria. Observed leak rates of tested Duolok tube fitting assemblies performed consistently better than the required Acceptance Criteria, and published competitive results.

Section 14: Bibliography, Equipment, References

Table 4.1: ASTM Material Standards

Standard	Material Shape	Description
A 182	Forged Fittings, Parts	Standard Specification for Forged or Rolled Alloy-Steel Pipe Flanges, Forged Fittings, and Valves and Parts for High-Temperature Service
A 276	Bars	Standard Specification for Stainless Steel Bars and Shapes
A 479	Bar, Shapes	Standard Specification for Stainless Steel Bars and Shapes for Use in Boilers and Other Pressure Vessels
B 16	Bar, Shapes	Standard Specification for Free-Cutting Brass Rod, Bar and Shapes for Use in Screw Machines
B 124	Bar, Shapes	Standard Specification for Copper and Copper Alloy Forging Rod, Bar, and Shapes
B 453	Bar, Shapes	Standard Specification for Copper-Zinc-Lead Alloy (Leaded-Brass) Rod
A 179	Tube	Standard Specification for Seamless Cold-Drawn Low-Carbon Steel Heat-Exchanger and Condenser Tubes
A 213	Tube	Standard Specification for Seamless Ferritic and Austinitic Alloy-Steel Boiler, Superheater, and Heat-Exchanger Tubes
A 249	Tube	Standard Specification for Welded Austenitic Steel Boiler, Superheater, Heat-Exchanger, and Condenser Tubes
A 269	Tubing	Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service
B 68	Tube	Standard Specification for Copper Tube, Bright Annealed
B 75	Tube	Standard Specification for Seamless Copper Tube
B 88	Tube	Standard Specification for Seamless Copper Water Tube

Table 4.2: Applicable Codes and Standards

Section	Test Description	
ANSI / ASME B 31.1	Power Piping Code	
ANSI / ASME B 31.3	Process Piping Code	
ANSI / ASME BPV Section VIII	Boiler & Pressure Vessel Code	
ISO 7257	Aircraft - Hydraulic tubing joints and fittings - Rotary flexure test	

Table 4.3: Validation Test Equipment

Section	Test Description	Test Equipment Description
3.1	Initial Makeup Test	1016702 Torque Wrench
3.2	Understatic Deserves Test	1279 Ashcroft Pressure Gage
3.2	Hydrostatic Burst Pressure Test	L-400 Maximator Liquid Pump
3.3	Lludraulia Immulaa Drassura Tast	PDCR 911 Druck Pressure Transducer
3.3	Hydraulic Impulse Pressure Test	451279 SSL 02B Ashcroft Pressure Gage
2.4	Danastad Danada Tast	DLE 15-75 Maximator Air Booster Pump
3.4	Repeated Remake Test	L-400 Maximator Liquid Pump
		FI-90 Force Indicator
3.5	Tension Force Test	31910 Load Cell
		DTM Dillon Tensile Tester
		42-05000W160S SC Hydraulic Engineering
3.6	Viloretian Characa / Fordunance Test	Booster Pump
3.6	Vibration Stress / Endurance Test	2100 Strain Gage Conditioner System
		THe Measurements Group
2.7	Intermix Assurance Test	DLE 15-75 Maximator Air Booster Pump
3.7	intermix Assurance lest	L-400 Maximator Liquid Pump
2.0	Interchance Assumes Test	DLE 15-75 Maximator Air Booster Pump
3.8	Interchange Assurance Test	L-400 Maximator Liquid Pump
3.9	Con Dunantura Londy Took	HP 224 McDaniels Pressure Gage
3.9	Gas Pressure Leak Test	DLE 15-75 Maximator Air Booster Pump
		3210 Applied Test Systems Split Furnace
3.10	Thermal Cycle, Thermal Shock Test	XT16 Athena Temperature Controller
		MS-40 Veeco Helium Leak Detector
3.11	Vacuum Test	MS-40 Veeco Helium Leak Detector
2.12	Low Temperature (Cryogenic)	MS-40 Veeco Helium Leak Detector
3.12	Helium Leak Test	Type K TC Themocouple

TRADEMARKS:

Duolok is a trademark of SSP Fittings Corp.

A-Lok, CPI are trademarks of Parker Hannifin Corporation
Swagelok is a trademark of Swagelok Co.
Gyrolok is a trademark of Hoke Incorporated

SSP Instrumentation Document Number: ILDTR/025-99

Report No:

Revision:

Total Pages:

Date: